DG-A-QS-01 Take-off - Dortech two-storey garage, Option A - Permitted Development (storage loft)

SUPPLY SCOPE: only the Nudura ICF formwork and associated accessories are in our price. Everything else is supplied in good faith from the model and must be checked by the relevant professional. QUOTATION - NOT FOR CONSTRUCTION. Quantities only - pricing to follow.

Footprint 4,858 x 5,061 (Nudura Bond, no stack joints) | pitch 30.5 deg | eaves 2,474 | ridge 3,950 | FFL 2,656 | garage door 3,500 x 2,286 | Q01 28.10.26

ICF formwork + accessories (our supply)

Item	Qty	Unit
Nudura 6in Standard straight form (2.6in Std, 96 x 18in)	50	nr
Nudura 6in Standard 90 deg corner form	20	nr
Total forms	70	nr
Opening end caps (left + right)	24	nr
Opening head lintel pieces	6	nr
Opening sill lintel pieces (W01)	2	nr
Raked feature opening sill closure 6in (L1-G01)	1.11	m
Stack joints	0	nr
ICF core concrete (approx., C32/40, 6in core)	6.14	m3

Structure (good faith)

Item	Qty	Unit
Raft slab 200 RC + 600 x 450 thickened edge (indicative)	7.53	m3
Hardcore 150 MOT Type 1 + DPM	2.12	m3
First floor: PS9-type metal-web joists 225 @400 (front-rear on gable ledgers)	13	nr
First floor deck: 22 Egger Protect P5	14.5	m2
Ridge beam (glulam)	100 x 320 GL24h x 5.36 m	1 nr
Rafters 47 x 147 C24 @400 (loose, cut roof, 3051 long)	24	nr
Gable ladders: barge + rail + outriggers 47 x 72 C24	40	nr

Windows + doors (good faith)

Item	Qty	Unit
L1-D02 composite door (48 slab, multi-point lock, vision panel)	901 x 2101 SO	1 nr
L1-W01 Alu-clad casement window (RAL 7016), 2 lights (2 opening)	1201 x 901 SO	1 nr
L1-G01 Raked aluminium feature glazing screen to the front gable (30.5 deg verges) (PPC, DGU, mullions <= 1000)	1110 x 577 SO	1 nr
L1-D01 Sectional garage door 3,500 x 2,286, low-headroom track (door supplier)	3500 x 2286 SO	1 nr

Dryvit 500 render (Tremco CPG)

Item	Qty	Unit
Dryvit 500 render - West (left)	10.27	m2
Dryvit 500 render - Rear (south)	12.63	m2
Dryvit 500 render - East (right)	11.35	m2
Dryvit 500 render - Front (north)	6.06	m2
Reveal returns (to the frames)	1.2	m2
Total render area	41.51	m2
Bell bead / base drip profile	15.4	m
PVC corner bead with mesh	9.0	m
Stop bead / termination profile (eaves + verges)	21.4	m
Reveal bead / window return profile	18.0	m
Tremco Dymonic 100 sealant (frame perimeters)	18.0	m
Reinforced Base Coat + Mesh: Genesis (Base Coat)	4	pail
Primer: Color Prime	2	5 gal pail
Finish Coat: DPR Sandpebble	4	65 lb pail
Reinforcing Mesh: Standard Mesh (4.3 oz)	47.9	m2
Diagonal mesh patches: Standard Mesh 300 x 200 at every opening corner	8	nr

Opening tapes (Tremco CPG illbruck)

Item	Qty	Unit
illbruck ME220 Exterior Window Membrane 100 mm (Tremco CPG)	12.2	m net (1 x 25 m rolls)
illbruck ME110 Interior Window Membrane 100 mm (Tremco CPG)	12.2	m net (1 x 25 m rolls)

Roof coverings + rainwater goods (good faith)

Item	Qty	Unit
Breathable roofing membrane (BS 5534 Type LR) incl. laps	37.6	m2
Treated battens 25 x 50 @ 345 gauge	117.9	m
Concrete interlocking tiles, slate grey	32.71	m2 (~337 tiles)
Dry ridge, half-round	5.36	m
Dry verge	12.2	m
Fascia 22 x 200 PVC-u	10.72	m
Soffit 10 PVC-u vented	2.14	m2
Barge boards 22 x 225 PVC-u (cover fascia + soffit ends)	12.2	m
Half-round gutter 112 black	10.72	m
Downpipes 68 round black	2	nr (4.42 m)