# DG-B-QS-01 Take-off - Dortech two-storey garage, Option B - Room in the roof (planning application)

SUPPLY SCOPE: only the Nudura ICF formwork and associated accessories are in our price. Everything else is supplied in good faith from the model and must be checked by the relevant professional. QUOTATION - NOT FOR CONSTRUCTION. Quantities only - pricing to follow.

Footprint 4,858 x 5,061 (Nudura Bond, no stack joints) | pitch 55.0 deg | eaves 2,474 | ridge 5,988 | FFL 2,656 | garage door 3,500 x 2,286 | Q01 28.10.26

### *ICF formwork + accessories (our supply)*

| Item | Qty | Unit |
|---|---|---|
| Nudura 6in Standard straight form (2.6in Std, 96 x 18in) | 67 | nr |
| Nudura 6in Standard 90 deg corner form | 20 | nr |
| Total forms | 87 | nr |
| Opening end caps (left + right) | 34 | nr |
| Opening head lintel pieces | 7 | nr |
| Opening sill lintel pieces (W01) | 2 | nr |
| Raked feature opening sill closure 6in (L1-G01) | 2.7 | m |
| Stack joints | 0 | nr |
| ICF core concrete (approx., C32/40, 6in core) | 6.56 | m3 |

### *Structure (good faith)*

| Item | Qty | Unit |
|---|---|---|
| Raft slab 200 RC + 600 x 450 thickened edge (indicative) | 7.53 | m3 |
| Hardcore 150 MOT Type 1 + DPM | 2.12 | m3 |
| First floor: PS9-type metal-web joists 225 @400 (front-rear on gable ledgers) | 12 | nr |
| First floor deck: 22 Egger Protect P5 | 17.85 | m2 |
| Ridge beam (glulam) | 100 x 320 GL24h x 5.36 m | 1 nr |
| Rafters 47 x 147 C24 @400 (loose, cut roof, 4583 long) | 24 | nr |
| Gable ladders: barge + rail + outriggers 47 x 72 C24 | 40 | nr |
| External steel stair: 13 x 200 / 250 (38.7 deg), landing 1,300 x 1,100, galv + PPC RAL 7016 | 1 | item |

### *Windows + doors (good faith)*

| Item | Qty | Unit |
|---|---|---|
| L1-D02 composite door (48 slab, multi-point lock, vision panel) | 901 x 2101 SO | 1 nr |
| L1-W01 Alu-clad casement window (RAL 7016), 2 lights (2 opening) | 1201 x 901 SO | 1 nr |
| L1-D03 composite door (48 slab, multi-point lock, vision panel) | 901 x 2101 SO | 1 nr |
| L1-G01 Raked aluminium feature glazing screen to the front gable (55.0 deg verges) (PPC, DGU, mullions <= 1000) | 2702 x 2429 SO | 1 nr |
| L1-D01 Sectional garage door 3,500 x 2,286, low-headroom track (door supplier) | 3500 x 2286 SO | 1 nr |

### *Dryvit 500 render (Tremco CPG)*

| Item | Qty | Unit |
|---|---|---|
| Dryvit 500 render - West (left) | 9.87 | m2 |
| Dryvit 500 render - Rear (south) | 15.21 | m2 |
| Dryvit 500 render - East (right) | 10.95 | m2 |
| Dryvit 500 render - Front (north) | 7.03 | m2 |
| Reveal returns (to the frames) | 1.8 | m2 |
| Total render area | 44.85 | m2 |
| Bell bead / base drip profile | 15.4 | m |
| PVC corner bead with mesh | 8.6 | m |
| Stop bead / termination profile (eaves + verges) | 27.1 | m |
| Reveal bead / window return profile | 27.0 | m |
| Tremco Dymonic 100 sealant (frame perimeters) | 27.0 | m |
| Reinforced Base Coat + Mesh: Genesis (Base Coat) | 5 | pail |
| Primer: Color Prime | 2 | 5 gal pail |
| Finish Coat: DPR Sandpebble | 5 | 65 lb pail |
| Reinforcing Mesh: Standard Mesh (4.3 oz) | 51.8 | m2 |
| Diagonal mesh patches: Standard Mesh 300 x 200 at every opening corner | 10 | nr |

### *Opening tapes (Tremco CPG illbruck)*

| Item | Qty | Unit |
|---|---|---|
| illbruck ME220 Exterior Window Membrane 100 mm (Tremco CPG) | 22.81 | m net (2 x 25 m rolls) |
| illbruck ME110 Interior Window Membrane 100 mm (Tremco CPG) | 22.81 | m net (2 x 25 m rolls) |

### *Roof coverings + rainwater goods (good faith)*

| Item | Qty | Unit |
|---|---|---|
| Breathable roofing membrane (BS 5534 Type LR) incl. laps | 56.5 | m2 |
| Treated battens 25 x 50 @ 345 gauge | 176.9 | m |
| Concrete interlocking tiles, slate grey | 49.14 | m2 (~506 tiles) |
| Dry ridge, half-round | 5.36 | m |
| Dry verge | 18.33 | m |
| Fascia 22 x 200 PVC-u | 10.72 | m |
| Soffit 10 PVC-u vented | 2.14 | m2 |
| Barge boards 22 x 225 PVC-u (cover fascia + soffit ends) | 18.33 | m |
| Half-round gutter 112 black | 10.72 | m |
| Downpipes 68 round black | 2 | nr (4.04 m) |